

**DEPARTMENT OF
PUBLIC WORKS**

815-724-4200 Direct
815-723-7770 Fax
Email: dortiz@joliet.gov



**150 WEST JEFFERSON STREET
JOLIET, ILLINOIS 60432-4158**

CITY OF JOLIET

APRIL 26, 2023

ADDENDUM NO. 1

**TO: 2023 SIDEWALK/ CURB REPLACEMENT PROJECT- CONTRACT B
Contract Number 2728-0623**

THE ATTENTION OF ALL PROSPECTIVE BIDDERS ON THE ABOVE REFERENCED PROJECT IS CALLED TO THE FOLLOWING LISTED MODIFICATION IN THE CONTRACT DOCUMENTS:

1. The earth and curb & gutter median island shall be partially removed and new curb & gutter installed at Mallard and Bronk Rd. as shown on the attached image. The pavement will be filled in with 7" PCC base course and 2"HMA (2" surface)
2. Attached is revised Schedule of Prices dated April 26, 2023.
3. Attached are the specification for the additional items Earth Median Removal and 7" PCC Base Course W/ 2" HMA (4" SUB-BASE GRANULAR MATERIAL).

The Acknowledgement of the Receipt of all Addendums must be printed clearly on the outside of your Bid Package or your Bid may not be opened.

**CITY OF JOLIET
SCHEDULE OF PRICES**

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	COST
NO. 1	P.C.C. SIDEWALK REMOVAL & REPLACEMENT, 5"	12000	SQ FT		
NO. 2	P.C.C. SIDEWALK, 5"	100	SQ FT		
NO. 3	CONCRETE CURB & GUTTER REMOVAL & REPLACEMENT	330	LN FT		
NO. 4	P.C.C. DRIVEWAY PAVEMENT REMOVAL & REPLACEMENT, 6"	120	SQ YD		
NO. 5	P.C.C. DRIVEWAY PAVEMENT REMOVAL & REPLACEMENT, 8"	30	SQ YD		
NO. 6	BUFFALO BOX/ VALVE BOX ADJUSTMENT	2	EACH		
NO. 7	HOT MIX ASPHALT REMOVAL & REPLACEMENT,3"	70	SQ YD		
NO. 8	DETECTABLE WARNINGS	150	SQ FT		
NO. 9	REMOVAL AND DISPOSAL OF CONTAMINATED MATERIAL	5	CU YD		
NO. 10	STRUCTURE TO BE ADJUSTED	2	EACH		
NO. 11	FRAME & LIDS TO BE FURNISHED AND INSTALLED, TY 1 F&OL	2	EACH		
NO. 12	TREE ROOT PRUNNING- 8" DIAMETER AND GREATER	8	EACH		
NO. 13	REGRAVING AND RESTORATION W/ EROSION CONTROL BLANKET	20	SQ YD		
NO. 14	EARTH MEDIAN REMOVAL	2.5	CU YD		
NO. 15	CURB & GUTTER REMOVAL	35	LN FT		
NO. 16	7" PCC BASE COURSE W/ 2" HMA SURFACE COURSE (4" SUB-BASE GRANULAR MATERIAL)	9	SQ YD		
BIDDER'S PROPOSAL FOR IMPROVEMENTS:					

CONTRACTOR NAME: _____

ADDRESS: _____

CITY/STATE/ ZIP: _____

TEL NO.: _____

XX1. **7" PCC BASE COURSE W/ 2" HMA SURFACE COURSE (4" SUB-BASE GRANULAR MATERIAL)**

This work will be completed per Article 311, 353, 354, and 406 of the Specifications but will exceed 6' in width. Tack coat shall be included in this work. The 4" sub-base granular material shall also be included in this work.

Method of Payment

This work will be paid for as measured in place per square yard per the contract item 7" PCC BASE COURSE W/ 2" HMA SURFACE COURSE (4" SUB-BASE GRANULAR MATERIAL)

XX2. **EARTH MEDIAN REMOVAL**


This work will be completed per Article 202 of the Specifications.

Method of Payment

This work will be paid for as measured in place per cubic yard per the contract item EARTH MEDIAN REMOVAL. No other compensation will be allowed.

MALLARD LN

BRONK RD



SCALE: 1" = 20' HORIZ