



NOTE;

1. PROPOSED CLEANOUT TO BE INSTALLED FLUSH TO THE EXISTING SURFACE.
2. CLEANOUT SHALL BE INSTALLED AS CLOSE TO BUILDING AS POSSIBLE
3. CONNECTIONS TO DISSIMILAR MATERIAL PIPES SHALL BE MADE WITH NON-SHEAR MISSION COUPLINGS WITH STAINLESS STEEL BANDS
4. CLEANOUTS IN PAVED AREAS SHALL BE INSTALLED WITH EAST JORDAN 1574 CAST IRON CLEANOUT. FRAME AND LID INSTALLED FLUSH WITH FINISHED SURFACE.

NOT TO SCALE

CITY OF JOLIET, ILLINOIS

SANITARY SERVICE
CLEANOUT DETAIL
SAN-13

DATE: NOVEMBER 2022