



NOTE:

- ALL CONNECTING PIPES SHALL BE PLUGGED WITH MECHANICAL WING PLUGS OF THE SPECIFIED DIAMETER AND TOPPED WITH CONCRETE PLUG. BRICK AND MORTAR PLUGS WILL NOT BE ACCEPTABLE IN LIEU OF CONCRETE.
- THE MINIMUM THICKNESS OF THE CONCRETE TO THE PLUG SHALL BE TWO PIPE DIAMETERS UP TO 24 INCHES.
- CONTRACTOR SHALL REMOVE FRAME, COVER, CONE AND ADJUSTMENT RINGS OF THE MANHOLE STRUCTURES, AND CONE/FLAT-TOP/WALL TO A MINIMUM OF TWO (2') FEET BELOW FINISHED GRADE.
- REMAINDER OF THE STRUCTURE IS TO BE FILLED WITH TRENCH BACKFILL.
- CONTRACTOR SHALL BE RESPONSIBLE FOR OFF-SITE DISPOSAL OF ADJUSTMENT RINGS, FRAME AND COVER MUST BE RETURNED TO THE CITY.

NOT TO SCALE

CITY OF JOLIET, ILLINOIS

STRUCTURE ABANDONMENT
SAN-15

DATE: NOVEMBER 2022