

# City of Joliet 2025 Water Main Improvements Pre-Bid Conference

October 30, 2024

#### **Pre-Bid Conference Overview**

#### **2025 Program Overview**


- Bid Groups
- Funding Programs

## Bidding and Contract Requirements

- Specifications and Measurement and Payment Review
- Key Contract Requirements

#### **Project Review**

- Bid Schedules
- Project Details



29 Miles of Water Main

#### **2025 Program Overview**

#### **Bid Group 1**

- Krings Acres Phase 2B
- Broadway (Theodore to Ruby)
- North Downtown
- Railroad Street

#### Bid Group 3

- Hickory Creek West
- Highland Phase 2
- Marquette Park
- North Prairie
- Reedwood Phase 3
- Twin Oaks Phase 1

#### **Bid Group 2**

- Emerald Lawns Phase 1
- Glenwood Manor
- Midland and Campbell
- Upper Bluff
- Virginia Phase 1

#### Bid Group 4 (Early 2025)

- Heggie Park Phase 1
- Washington Street

#### **Funding Programs**

- IEPA State Revolving Fund
  - 8 Projects
  - Water Main Improvements
  - Lead Service Line Replacement
- WIFIA Federal Funding
- COJ Water & Sewer Funds

#### **Bidding Requirements**

#### **City of Joliet**

- Prequalification (include with Bid or email to <u>lschuld@baxterwoodman.com</u>)
- City of Joliet Procurement Code
- Local Bidder Ordinance does not apply
- City's 10% minority participation
- City of Joliet Affidavits
- Download documents from City website and sign up for RSS feed
- Check City website for addenda

#### **Federal Funding Requirements**

- Advertise for DBEs in daily regional paper
  - One advertisement is acceptable for multiple projects, must meet earliest date
- Provide list of all subcontractors
  - Can use DBE Form #4
- Davis-Bacon or Illinois Prevailing Wage Act, whichever is higher
- Use of American Iron and Steel
- Employment of Illinois Workers on Public Works Act may apply
- Illinois Works Jobs Program Act Apprenticeship Initiative
- Project sign posted at job site

#### **Specifications and Measure and Payment**

- Bid Submittal Checklist for IEPA loan requirements
- Contractor badges required prior to entering homes
- Licensed plumber required for all water services
- Trench backfill tables in M&P
- RJT tables in Standard Details
- Pavement restoration thicknesses in General Notes
- Preconstruction video is incidental to the cost of water main


#### **Key Notes**

- Pipe material varies by project/location. Some locations require Ductile Iron Pipe, as noted
- Sanitary Lateral Secondary Locates

#### **Work Areas and Liquidated Damages**

- Work in multiple Work Areas is allowed but will not extend any Work Area's completion times
- Deviations to Work Areas must be submitted to the City at the Pre-Construction meeting for approval
- Contract time will commence upon any intrusive work to earth or pavement (sawcutting, milling, excavation, potholing, etc.)

Description of Interim Milestone Liquidated Damages	Dollar Amount
Water Main and Water Service Completion of individual Work Area not completed within specified time	\$500/day
Pavement restoration of individual Work Area not completed within specified time	\$500/day
Unscheduled work occurring without required notice to residents as outlined in Section 33 11 43	\$500/property for each occurrence
Traffic Control Deficiency per MUTCD requirements as specified in 01 50 00	\$1,000/day



#### **Digital Utility Data Collection Requirements**

- Survey all exposed or installed water, sanitary, and storm utilities
- Contractor to provide their own GPS unit or rent from supplier
- Contractor must provide a smart phone or tablet with 5G connectivity
- City of Joliet will provide one ESRI license per project
- City staff will not provide technical support of the GPS units
- A 2-hour training session will be provided at the start of construction and support up to 4 hours per month
  - The cost for additional support is not included in this project. Contractors are recommended to establish a working relationship with a GPS support consultant to provide as-needed assistance



#### Road Closure Permit

- Required for road closures that last 20 minutes or more that do not have a detour in place
- Liquidated damages of \$25,000 per day, per occurrence for unapproved closures

## Traffic Control and Protection

- Limited to 5% of sum of all other pay items
- Includes maintaining pedestrian access

## **Testing Against Existing Valves**

 Contractor can test against existing valves or against a cap; plans indicate locations where existing valves are new



#### NOTICE OF START OF WATER MAIN REPLACEMENT WORK

City of Joliet Department of Public Utilities 815-724-4220









#### NOTICE OF TEMPORARY WATER OUTAGE

As part of the City's water main replacement program, water to your property will be off for water main replacement work at the below date and times.

Please visit the City's website for project updates at Joliet.gov/Construction-Zone

AM / PM

CITY OF JOHET

AVISO DE CORTE

TEMPORAL DE AGUA

Como parte del programa de Reemplazo de la tubería principal de agua de la Ciudad, se cortará el suministro de agua a su propiedad debido al trabajo de reemplazo de la

Visite el sitio web de la ciudad

Departamento de Servicios

Públicos de la Ciudad de Joliet 815-724-4220

JOHET



#### NOTICE OF WATER SERVICE REPLACEMENT

As part of the City's water main replacement program, water service to your property will be affected on the below date. The water outage will usually last less than one hour. You may experience air build-up within your water lines. It is recommended to run water for five minutes to remove any air build-up.

Please visit the City's website

City of Joliet Public Utilities Department 815-724-4220

JOHE

**AVISO DE REEMPLAZO** 

DE SERVICIO DE AGUA

DE SERVICIO DE AGUA
Como parte del programa de
reemplazo de tuberias principales
de opus de la Cuudad, el servicio de
agua de su propiedad se verá
supun de su propiedad se verá
supun de su propiedad se verá
supun de su propiedad se verá
le corte de paga seule durar menos
de una hora. Es possible que puede
de suprementar una acumulación de
aire dentro de las lineas de agua.
de recemienta dejar cerrer el agua
cualquier acumulación de sirve.

Cualquier acumulación de sirve.

JOHET



#### LANDSCAPE RESTORATION UPDATE

The City's water main replacement work adjacent to your address has been completed. The landscape restoration work will be completed when the weather is conducive for grass to be planted.

Please visit the City's website for project updates at Joliet.gov/Construction-Zone

CITY OF JOLIET



#### ACTUALIZACIÓN DE RESTAURACIÓN DEL PAISAJE

Se ha completado el trabajo de reemplazo de la tubería principal de agua de la ciudad adyacente a su dirección. El trabajo de restauración del paisaje, se completará cuando el clima sea propicio para plantar cisped.

Visite el sitio web de la ciudad para actualizaciones del proyecto en Joliet.gov/Construction-Zone

Departamento de Servicios Públicos de la Ciudad de Joliet 815-724-4220

Visite el sitio web de la ciudad para actualizaciones del proyecto en Joliet.gov/Construction-Zone Ven la fecha al otro lado cuando el trabajo de restauración del paisaje está programado para comenzar. Departamento de Servicios Públicos de la Ciudad de Joliet 815-724-4220




#### **Resident Notifications**

- **Start of Water Main Work**
- **Temporary Water Outage**
- **Water Service Replacement**
- **Landscape Restoration**

#### **Lead Service Line Workflow**

- Project Management Pay Item
  - Participant: 3 hours
  - Non-participant (known lead): 1 hour
- Sample Workflow and Forms in Project Manual
- Notification/Replacement Timeline
  - Comply with IEPA and IDPH Requirements
  - For Known/Suspected Lead:
    - City to notify of project minimum 45 days, additional attempts required if no response
    - · Pre-construction sampling
    - Notify 14 days prior to LSL replacement
  - For Lead Discovered During Construction, notify City immediately

**Lead Services Expected in 13 Projects** 



Project	Last Day for DBE Ads	Last Day for Questions	Bid Ope	ning
Broadway (Theodore to Ruby)	11/2/2024	11/11/2024	11/18/2024	10:00 AM
North Downtown	11/3/2024	11/11/2024	11/19/2024	10:00 AM
Railroad St	11/3/2024	11/11/2024	11/19/2024	2:00 PM
Krings Acres Phase 2B	11/4/2024	11/11/2024	11/20/2024	2:00 PM

#### **Broadway (Theodore to Ruby)**



10,300 feet of 6" – 12" DI

Estimated Notice to Proceed: 4/1/25

Substantial Completion: 150 days

Final Completion: 180 days

**Expected Lead Service Lines** 

Soil boring logs included in appendices. LPC 663 to be signed

Work within IDOT ROW. Detour required; Bond amount: \$1M

Storm sewer extension and sanitary abandonment

Easement coordination with church

#### **North Downtown**



10,600 feet of 6" – 12" DI
- Includes 320 feet of 10" CIPP

Estimated Notice to Proceed: 4/1/25

Substantial Completion: 210 days

Final Completion: 240 days

**Expected Lead Service Lines** 

Soil boring logs included in appendices. LPC 663 to be signed

Work within IDOT ROW. Detour required; Bond amount: \$1M

Two railroad viaduct crossings

Pedestrian MOT plan required

#### **Railroad Street**



3,100 feet of 6" - 12" DI

Estimated Notice to Proceed: 8/1/25

Substantial Completion: 60 days

Final Completion: 90 days


**Expected Lead Service Lines** 

Soil boring logs included in appendices. LPC 663 to be signed

Work within IDOT ROW. Detour required; Bond amount: \$200,000

One railroad crossing; abandonment required at second crossing

#### **Krings Acres Phase 2B**



7,700 feet of 8", DI or PVC

Estimated Notice to Proceed: 4/1/25

Substantial Completion: 90 days

Final Completion: 120 days

City will complete pH testing and sign

LPC-662

Project	Last Day for DBE Ads	Last Day for Questions	Bid Ope	ning
Glenwood Manor	11/17/2024	11/26/2024	12/3/2024	10:00 AM
Upper Bluff	11/17/2024	11/26/2024	12/3/2024	2:00 PM
Midland and Campbell	11/18/2024	11/26/2024	12/4/2024	10:00 AM
Emerald Lawns Phase 1	11/19/2024	11/26/2024	12/5/2024	10:00 AM
Virginia Phase 1	11/19/2024	11/26/2024	12/5/2024	2:00 PM

#### **Glenwood Manor**



15,900 feet of 6" – 12", DI or PVC

Estimated Notice to Proceed: 3/15/25


Substantial Completion: 150 days

Final Completion: 180 days

Local detour required

City will complete pH testing and sign LPC-662

#### **Upper Bluff**



12,300 feet of 6" – 12", DI or PVC - Includes 1,000 feet of 8" via HDD

Estimated Notice to Proceed: 6/1/25

Substantial Completion: 180 days

Final Completion: 210 days

**Expected Lead Service Lines** 

Soil boring logs included in appendices. LPC 663 to be signed

Work within IDOT ROW. No detour required; Bond amount not yet determined

Coordinate sequencing with university

Storm sewer extension and tunnel abandonment

Rear yard service abandonments

#### Midland and Campbell



6,700 feet of 8" - 16", DI or PVC

Estimated Notice to Proceed: 7/1/25

Substantial Completion: 90 days

Final Completion: 120 days

**Expected Lead Service Lines** 

Coordinate connection near pump station with City operations staff

Coordinate sequencing with school

#### **Emerald Lawns Phase 1**



15,100 feet of 6" – 12", DI or PVC

Estimated Notice to Proceed: 5/1/25

Substantial Completion: 150 days


Final Completion: 180 days

**Expected Lead Service Lines** 

City will complete pH testing and sign LPC-662

Coordinate sequencing with school

#### Virginia Phase 1



5,200 feet of 6" - 8", DI or PVC

Estimated Notice to Proceed: 3/15/25

Substantial Completion: 50 days

Final Completion: 80 days

**Expected Lead Service Lines** 


Soil boring logs included in appendices. LPC 663 to be signed

Work within IDOT ROW. No detour required; Bond amount not yet determined

Work in easement for alleyway main

Project	Last Day for DBE Ads	Last Day for Questions	Bid Ope	ning
Marquette Park	11/23/2024	12/2/2024	12/9/2024	10:00AM
Hickory Creek West	11/23/2024	12/2/2024	12/9/2024	2:00PM
North Prairie	11/24/2024	12/2/2024	12/10/2024	10:00AM
Reedwood Phase 3	11/24/2024	12/2/2024	12/10/2024	2:00PM
Twin Oaks Phase 1	11/25/2024	12/2/2024	12/11/2024	10:00AM
Highland Phase 2	11/25/2024	12/2/2024	12/11/2024	2:00PM

#### **Marquette Park**



11,100 feet of 6" – 16", DI or PVC

Estimated Notice to Proceed: 5/1/25

Substantial Completion: 150 days

Final Completion: 180 days

**Expected Lead Service Lines** 


City will complete pH testing and sign LPC-662

Work within IDOT ROW. No detour required; Bond amount not yet determined

Rear yard service abandonments in easement

Coordinate sequencing with school

#### **Hickory Creek West**



12,800 feet of 6" – 12", DI or PVC - Includes 800 feet of 8" via HDD

Estimated Notice to Proceed: 5/1/25

Substantial Completion: 150 days

Final Completion: 180 days

**Expected Lead Service Lines** 

Soil boring logs included in appendices.

LPC 663 to be signed

#### **North Prairie**



12,000 feet of 6" – 12", DI or PVC

Estimated Notice to Proceed: 6/1/25


Substantial Completion: 120 days

Final Completion: 150 days

**Expected Lead Service Lines** 

City will complete pH testing and sign LPC-662

#### **Reedwood Phase 3**



7,200 feet of 6" – 16", DI or PVC

Estimated Notice to Proceed: 4/1/25

Substantial Completion: 120 days


Final Completion: 150 days

**Expected Lead Service Lines** 

City will complete pH testing and sign LPC-662

Rear yard service abandonments

#### **Twin Oaks Phase 1**



5,300 feet of 6" – 8", DI or PVC
- Includes 200 feet of 8" HDPE via HDD


Estimated Notice to Proceed: 3/15/25

Substantial Completion: 70 days

Final Completion: 100 days

City will complete pH testing and sign LPC-662

#### **Highland Phase 2**



6,400 feet of 8" – 12", DI or PVC

Estimated Notice to Proceed: 7/1/25

Substantial Completion: 60 days

Final Completion: 90 days

City will complete pH testing and sign LPC-662

Work within IDOT ROW. No detour required; Bond amount not yet determined

Coordinate connection near elevated tank with City operations staff

# Bidding Requirements Important Dates

	Bid Group 1	Bid Group 2	Bid Group 3
Last Day for DBE Ads	November 2-4	November 17-19	November 23-25
Last Day for Questions	November 11	November 26	December 2
Bid Openings	November 18-20	December 3-5	December 9-11

One advertisement is acceptable for multiple projects, must meet earliest date

#### Bid Group 4

#### **Heggie Park Phase 1**

- Approximately 8,000 feet of 8" 20"
- Complexities
  - •Three railroad crossings
  - •Coordinate connection at WTP with City operations staff
  - Local detours required

#### **Washington Street**

- Approximately 3,800 feet of 8" 20"
- Complexities
  - One railroad crossing
  - •Coordinate connection near pump station with City operations staff
  - Local detour required

#### **Tentative Timeline**

- Advertise for Bids: Late January
- **Bid Opening: Late February**
- Award: Early March
- NTP: April



Please sign attendance sheet

Contact information in Advertisement for Bids and Bidder Instructions